






GROUP A :

4 x EXISTING TOILETS  
4 x TOILETS TO BE REHABILITATED  
0 x EXISTING STANDPIPES  
0 x STANDPIPES TO BE REHABILITATED



Replace wash basin and plumbing items. Replace steel doors with locks.

Replace complete toilet, poly cop pipe with connectors and fittings and repair toilet plumbing. Replace steel door with lock.





Replace seat and cover set.




Replace whole structure with new precast structure.

GROUP B :

10 x EXISTING TOILETS  
6 x TOILETS TO BE REHABILITATED  
0 x EXISTING STANDPIPES  
0 x STANDPIPES TO BE REHABILITATED





Remove 10 wash basin taps.



Replace seat / cover set. Fix toilet plumbing problems.

Replace seat / cover set.

Replace complete toilet, poly cop pipe with connectors and fittings and repair toilet plumbing.





Replace seat / cover set.


Replace cistern and seat / cover set.

GROUP C :


2 x EXISTING TOILETS  
2 x TOILETS TO BE REHABILITATED  
0 x EXISTING STANDPIPES  
0 x STANDPIPES TO BE REHABILITATED






Replace seat and cover set and cistern



Replace plumbing system.






Compact G7 filling around toilets.



GROUP E :




8 x EXISTING TOILETS  
8 x TOILETS TO BE REHABILITATED  
0 x EXISTING STANDPIPES  
0 x STANDPIPES TO BE REHABILITATED





Replace cistern, toilet seat and cover set.

Fix cistern.

Replace cistern, poly cop pipe with connectors and fittings.




Replace seat and cover set.









Fix outlet plumbing.

Replace some steel doors with locks.



GROUP D :

4 x EXISTING TOILETS  
4 x TOILETS TO BE REHABILITATED  
0 x EXISTING STANDPIPES  
0 x STANDPIPES TO BE REHABILITATED



Replace pan, cistern, seat, poly cop pipe with connectors and fittings and repair toilet plumbing. Replace wash basin with taps and plumbing items. Replace steel doors with locks.

GENERAL NOTES:

RESPONSIBLE PERSONS

DRAWN	SIGNATURE	DATE
DESIGNED		
CHECKED		

THE MASTER HELD AT THE AURECON GEORGE OFFICE BEARS THE SIGNATURE OF APPROVAL

aurecon

www.aurecongroup.com

CLIENT

MOSSELBAY MUNICIPALITY

REV	DATE	REVISION DETAILS	APPROVED

PROJECT

MOSSEL BAY ABS

TITLE

REHABILITATION OF INTERM BASIC SERVICES  
KWANONQABA : SEWENDELAAN

DRAWN	DESIGNED	FOR DISCUSSION PURPOSES ONLY	
A VAN WYK	E WITBOOI	PROJECT No.	
CHECKED		113408	
M BOTHA		SCALE	SIZE
APPROVED		1 : 1000	A0
AC KEYSER	DATE	DRAWING No.	REV
12/04/2018		113408 GE 507	A