GROUP A :
8 x EXISTING TOILETS
6 x TOILETS TO BE REHABILITATED
0 x EXISTING STANDPIPES
0 x STANDPIPES TO BE REHABILITATED

Construct "gully" complete including 250mm concrete manhole ring, long radius 90° bend and PVC gully and grate. Repair outlet toilet PVC pipes.

Replace steel doors.

Replace cistern, seat and cover set.

Repair leakage.

Replace cistern and repair leakage.

Replace cistern.

GROUP B :
8 x EXISTING TOILETS
4 x TOILETS TO BE REHABILITATED
0 x EXISTING STANDPIPES
0 x STANDPIPES TO BE REHABILITATED

Replace steel doors.

Replace seat and cover set.

Construct "gully" complete including 250mm concrete manhole ring, long radius 90° bend and PVC gully and grate. Repair outlet toilet PVC pipes.

Replace cistern, seat and cover set.

GROUP C :
3 x EXISTING TOILETS
1 x TOILETS TO BE REHABILITATED
0 x EXISTING STANDPIPES
0 x STANDPIPES TO BE REHABILITATED

Construct "gully" complete including 250mm concrete manhole ring, long radius 90° bend and PVC gully and grate.

Replace seat and cover set.

GENERAL NOTES:

RESPONSIBLE PERSONS		
	SIGNATURE	DATE
DRAWN		
DESIGNED		
CHECKED		

THE MASTER HELD AT THE AURECON GEORGE OFFICE BEARS THE SIGNATURE OF APPROVAL

aurecon
www.aurecongroup.com

CLIENT

MOSSEL BAY MUNICIPALITY

REV	DATE	REVISION DETAILS	APPROVED

PROJECT

MOSSEL BAY ABS

TITLE

REHABILITATION OF INTERM BASIC SERVICES
KWANONQABA : THEMBANI STREET

DRAWN	DESIGNED	FOR DISCUSSION PURPOSES ONLY
A VAN WYK	E WITBOOI	
CHECKED		PROJECT No.
M BOTHA		113408
APPROVED		SCALE / SIZE
		1 : 750 / A0
AC KEYSER ECSA -20067/188	DATE	DRAWING No. / REV
		113408 GE 516 / A